

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-21,011-0000

LEASE NAME Dreitz

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-11

1680 Ft. from S Section Line

3600 Ft. from E Section Line

LEASE OPERATOR Shepler & Thomas, Inc.

SEC. 11 TWP. 32S RGE. 31 (R) or (W)

ADDRESS P.O. Box 1162, Liberal, KS 67905-1162

COUNTY Seward

PHONE# (316) 624-0750 OPERATORS LICENSE NO. 3711

Date Well Completed 4-20-88

Character of Well Dry

Plugging Commenced 7-1-88

(Oil, Gas, (D&A) SWD, Input, Water Supply Well)

Plugging Completed 7-1-88

The plugging proposal was approved on _____ (date)

by Dodge City - Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation N/A Depth to Top N/A Bottom N/A T.D. 6000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER **RECEIVED**
STATE CORPORATION COMMISSION

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	AUG 10 1988			8 5/8	1629	None
				4 1/2	5999	3015

Describe in detail the well in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. CIBP @ 5858 with 1 sk cement on top, water to 4840. CIBP @ 4840 with 1 sk of cement. Mud to 1616', 50 sk 60/40 poz from 1616 to 1516, Mud to 750, 30 sk from 750-650, mud to 40'. 10 sks of cement @ 40 to 0 Cut off 8 5/8 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506, Liberal, KS 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: SHEPLER & THOMAS, INC.

STATE OF KANSAS COUNTY OF SEWARD, ss.

R. F. Burke

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R F Burke

(Address) P.O. Box 1162, Liberal, KS 67905-1162

SUBSCRIBED AND SWORN TO before me this 8th day of August, 1988

Sharon E. Freeman

Notary Public
Sharon E. Freeman

My Commission Expires: 01-04-91

