

15-175-10122-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Get All Information Completely
Made Required Affidavit
Make or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Seward County, Sec. 9 Twp. 32S Rge. (X) 31 (W)

Location as "NE/CNWxSWx" or footage from lines C NW SE SE

Lease Owner SUNBAY MID-CONTINENT OIL COMPANY

Lease Name P. Collins Well No. 1

Office Address Box 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 6 19 57

Application for plugging filed September 6 19 57

Application for plugging approved September 9 19 57


Plugging commenced September 6 19 57

Plugging completed September 6 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Depth to top Bottom Total Depth of Well 5810 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1426'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 650', set HOWCO plug with 35 sacks cement on top of plug.
Filled with mud to 35', 1 sack hulls with 15 sacks cement. Cement to surface.
Plugging completed.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Company

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

N. E. Montgomery (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery
Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of September, 19 57

Houlihan Notary Public.

My commission expires December 24, 1960

9-17-57

PLUGGING
FILE SEC 9 T 32 R 31 W
BOOK PAGE 43 LINE 5

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
September 9, 1957

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: August 3, 1957
Drilling Completed: September 6, 1957

P. Collins #1 -
Sec. 9-32S-31W,
Seward County, Ks.

DRILLERS LOG

Depth Figures Indicate Base of Formation

Sand	375
Sand & Shells	500
Red Bed & Shells	654
Lime & Red Bed	657
Red Bed & Shells	1129
Shale & Shells	2085
Lime & Shale	2315
Shale & Lime	2535
Lime & Shale	2950
Lime	3070
Lime & Shale	3220
Lime	3325
Lime & Shale	3405
Lime	3530
Lime & Shale	3705
Lime	4200
Lime & Shale	4319
Lime	4958
Lime & Shale	5042
Lime	5332
Lime & Shale	5372
Lime	5448
Lime & Shale	5605
Shale & Lime	5620
Lime & Shale	5716
Lime, Shale, & Chert	5754
Lime & Shale	5810 TD

I, Frank E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company's P. Collins #1 - Section 9-32S-31W, Seward County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

STATE OF KANSAS
MINERAL COMMISSION

SEP 17 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING			
FILE	SEC 9	T 32	R 31W
BOOK	PAGE 43	LINE 5	