

15-175-20025-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Seward County, Sec. 6 Twp. 32S Rge. (E) 1W (W)

Location as "NE/CNW/SW" or footage from lines NW NW  
Lease Owner William Gruenerwald & Associates, Inc.  
Lease Name Woodworth Well No. 2  
Office Address P. O. Box 909, Colorado Springs, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 6 19 68  
Application for plugging filed January 6 19 68  
Application for plugging approved January 6 19 68  
Plugging commenced January 6 19 68  
Plugging completed January 6 19 68  
Reason for abandonment of well or producing formation No producible shows



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 6000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1640'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 900'; 35 sx cement from 900' to 800'; heavy mud to 45'; 15 sx cement from 45' to 0'.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 16 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Garvey Drilling Company  
Address Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Verne A. Morris (employee of owner) or ~~owner or operator~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris  
Garvey Drilling Company, Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of February, 19 68

My commission expires November 5th, 1969

Richard A. Boy  
Notary Public.

# WELL LOG

COMPANY **Wm Gruenerwald & Assoc., Inc.**

SEC. **6** T. **32S** R. **31W**

FARM **Woodworth**

NO. **2**

LOC. **W/2 NW**


TOTAL DEPTH **6000'**

COUNTY **Seward**

COMM. **12-15-67**

COMP. **1-6-68**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 1640' w/820 sx cement**

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 550' Sand
- 1175' Red Bed
- 1325' Sand
- 1365' Red Bed and Shale
- 1640' Red Bed and Sand
- 2190' Shale and Shells
- 2280' Shale and Lime
- 2450' Shale
- 3140' Shale and Lime
- 3270' Shale and Chalky Lime
- 4354' Shale and Lime
- 4515' Lime
- 4590' Lime and Shale
- 5195' Lime
- 5707' Lime and Shale
- 5905' Lime
- 5809' Lime and Chert
- 6000' Lime
- 6000' RTD

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 16 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas

County of Barton

I, Sam H. Stephens

of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Woodworth No. 2 well.

*Sam H. Stephens*

Subscribed and sworn to before me this 12th day of January 1968

My Commission Expires: November 5th, 1969

*Richard D. [Signature]*  
NOTARY PUBLIC