

15-119-10122-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Meade SEC. 36 TWP. 32S RGE. 30W E/W
Location as in quarters or footage from lines:
C. N.E. S.W.

Lease Owner Kaiser Frances Oil Co.
Lease Name Bachman Well No. 2
Office Address Box 746 Perryton, Texas 79070
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 6-21-57
Application for plugging filed 2-1-83
Plugging commenced 5-4-83
Plugging completed 5-7-83
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation Morrow Sand Depth to top 5661 bottom 5696 T.D. 5824
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Morrow	Oil	5673	5690	9 5/8	1612	none
				5 1/2	5814	2616

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

- Pump 25 sks. of cement & 2 sks. of hull's @ 5690 to 5400
- Pump 40 sks. of cement @ 1650
- Pump 20 sks. of cement @ 500 to 460
- Put 10 sks. of cement @ 40 to 0
- Cut off & cap 9 5/8 3' below ground level.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Tulsa, ss.
Drew Tyler (employee of owner) or (~~owner or operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Drew Tyler
P.O. Box 535528, Tulsa, OK 74153
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 83

Donna M. Knapp
Notary Public.
STATE CORPORATION COMMISSION

My Commission expires: Nov. 22, 1986

JUN 20 1983

CONSERVATION DIVISION
Wichita, Kansas