


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Seward County, Sec. 28 Twp. 32 Rge. (E) 31 (W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Musgrove Petroleum Corporation
Lease Name COLLINGWOOD Well No. 1
Office Address 518 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed May 11, 19 55
Application for plugging filed May 17, 19 55
Application for plugging approved May 18, 19 55
Plugging commenced July 11, 19 55
Plugging completed July 11, 19 55
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5775 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	578'	None
				8-5/8"	2719 1/2	1131'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 575'.
Set 1st plug at 575' w/30 sx cement.
Filled hole with mud to 20'.
Set 2nd plug at 20' w/15 sx cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Arnett (Jayhawk) Casing Pulling
Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Gordon L. Koelling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of July, 19 55

Alma E. Kase
Notary Public.

My commission expires July 16, 1955

PLUGGING
FILE SEC 28 T 32 R 31 W
BOOK PAGE 119 LINE 39

STATE CORPORATION COMMISSION
JUL 15 1955
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	COLLINGWOOD #1
LOCATION:	C NE SW, Sec. 28-32-31 Seward County, Kansas
COMMENCED:	April 16, 1955
COMPLETED:	May 11, 1955

0	50	Sand
50	520	Sand & clay
520	530	Red Bed
530	580	Shale & red bed
580	820	Red shale & lime streaks
820	950	Sand & red bed
950	995	Anhydrite
995	1040	Anhydrite & shale
1040	1460	Sand & shells
1460	1664	Red shale & shells
1664	1700	Shale & lime shells
1700	1752	Shale & shells
1752	1783	Lime
1783	1820	Shale
1820	2225	Lime & shale
2225	2365	Anhydrite & shale
2365	2435	Anhydrite & lime
2435	2575	Anhydrite
2575	2612	Anhydrite & lime shells
2612	2755	Lime
2755	2934	Lime & shale
2934	3081	Lime
3081	3449	Lime & shale
3449	3540	Lime
3540	3686	Lime & shale
3686	3939	Lime
3939	4050	Lime & shale
4050	4312	Lime
4312	4400	Lime & shale
4400	4853	Lime
4853	4945	Lime & shale
4945	5560	Lime
5560	5590	Lime & shale
5590	5775	Lime
	5775	Rotary Total Depth

Set 13-3/8" surface casing at 578' with 525 sacks cement, 1% calcium chloride.

Set 8-5/8" intermediate pipe at 2719 1/2' with 225 sacks cement, 1% calcium chloride.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

PLUGGING
MAY 28 1955
MAY 19 1955

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the COLLINGWOOD #1, C NE SW, Section 28-32-31, Seward County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1955
CONSERVATION DIVISION
Wichita, Kansas

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 17th day of May, 1955.

Notary Public
Notary Public