

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION FORM CP-1
Rev. 6/4/84

JUN 9 1989
06-09-89
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-151-21181 - 00-00 (of this well) 6/89
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Falcon Exploration Inc. OPERATORS LICENSE NO. 5316

ADDRESS 125 N. Market, Ste. 1075, Wichita, KS 67202 PHONE # (316) 262-1378

LEASE (FARM) Hissons WELL NO. 2 WELL LOCATION W/2 NW SW COUNTY Pratt

SEC. 2 TWP. 28S RGE. 12 (E) or (W) TOTAL DEPTH 4550 PLUG BACK TD 4151'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 10 3/4 SET AT 279' CEMENTED WITH 175 SACKS

CASING SIZE 4 1/2 SET AT 4168 CEMENTED WITH 150 SACKS

PERFORATED AT 3965'-68' 4001'-04', 4058'-60'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand to 3900', bail 4 sx cmt on top.

Shoot off and pull 4 1/2" casing. Mix & pump as follows: 400 sx hulls, 10 sx gel, 50 sx

cement, 10 sx gel, 100# hulls, 10 3/4" wiper plug, 130 sx cmt. Cut of 10 3/4" 3' below grade

(If additional space is needed use back of form) Cement: 60/40 poz, 6% gel

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Butch Hoberecht (Gear Petroleum Co.) PHONE # (316) 721-5325

ADDRESS 125 N. Market, #1075, Wichita, KS 67202

PLUGGING CONTRACTOR Great Bend Casing Pulling LICENSE NO. 4635

ADDRESS Box 768, Great Bend, KS 67530 PHONE # (316) 792-6970

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: J. E. Boyce
(Operator or Agent)

DATE: 6/7/89

1



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH H. HENLEY CHAIRMAN
ERIC KOWALEWSKI COMMISSIONER
FRANCIS WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
SEP 12 1989
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

June 12, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Falcon Exploration, Inc.
125 N. Market, Ste. 1075
Wichita, KS 67202

Hissons #2
W/2 NW SW
Sec. 02-28S-12W
Pratt County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760