

15-189-00671-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA (SPUD 12/14/46)

LEASE NAME SMITH

WELL NUMBER 1-14

1390 Ft. from N Section Line

1250 Ft. from W Section Line

SEC. 14 TWP. 34S RGE 39 (E) or (W)

COUNTY STEVENS

Date Well Completed 1946

Plugging Commenced 05/05/97

Plugging Completed 05/12/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/22/97 (date)

by MR. STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation CHASE Depth to Top 2619' Bottom 2777' T.D. 2785'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2619'	2777'	10-3/4"	561'	3'
				7"	2619'	3'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set, MIRU PU, RIH W/CIBP & SET @ 2560. TIH W/2-3/8" TBG TO 2560. SPOT 2 SXS CMT ON CIBP. CIRC HOLE W/9 PPG MUD. TOH W/2-3/8" TBG. RIH W/CBL. LOG FROM 960 TO 400. TOC @ 865. RIH W/3-3/8" PERF GUN & PERF 610-611 W/4 SPF, 90 DEG PHASING, TS = 45' PMP DWN 7" CSG W/141 SXS CMT, 14.5 BBL 9 PPG MUD, 9 SXS CMT. CIRC 5 BBLs OUT OF SF CSG/PROD CSG ANNULUS. RDMO PU CUT OFF. CAP & INSCRIBE 10-3/4" & 7" CSG 3' BELOW GL. NOTIFIED KCC REP STEVE MIDDLETON. RESTORE LOCATION. (WELL REDRILLED AS HERBEL A-4)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 498A, TYRONE, OK 73951-9731 PHONE: (405) 854-6515 7-25-97

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1997

Shirley J. Childers
Notary Public

My Commission Expires:

