

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20,971-0000

LEASE NAME Dole "A"

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3960 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 4 TWP. 34S RGE. 39 ~~W~~ or (W)

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 4-27-89

Character of Well Gas

Plugging Commenced 4-24-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-29-91

The plugging proposal was approved on March 4, 1991 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow "D" Depth to Top 5980 Bottom 6000 T.D. 6900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Gas	Surface	1779	8 5/8	1779	0
				4 1/2	6345	3816'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Pulled 2 jts 2 3/8" tbg. Spot 500# cottonseed hulls & 20 sxs cmt @ 5980' dwn tbg, fl w/mud. Circ hole w/mud, TOH w/tbg. Shot off csg @ 5200'. Free csg @ 3816'. TOH w/csg to 2700'. Spotted 35 sxs @ 2700', .50 sxs @ 1879'-1679', 20 sxs 850'-750', 15 sxs 50' to surface. Rec 3816' 4 1/2" csg. State witness. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams  
Beverly J Williams, Engineering Tech.  
(Address) P.O. Box 351, Liberal, KS 67905-0351

RECEIVED

STATE CORPORATION COMMISSION

MAY 09 1991

SUBSCRIBED AND SWORN TO before me this 8th day of May, 19 91

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires: \_\_\_\_\_



Notary Public