

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20245-0000
LEASE NAME NIX "B"
WELL NUMBER 1

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

2450 Ft. from N Section Line

1250 Ft. from W Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

SEC. 03 TWP. 34S RGE 39 (E) or (W)

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

COUNTY STEVENS

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 7-13-77

Character of Well GAS

Plugging Commenced 11-29-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-30-98

The plugging proposal was approved on 11-18-98 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 2930 Bottom 2979 T.D. 2985

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
COUNCIL GROVE	GAS	2930	2979	8-5/8"	429	0
				5-1/2"	2985	100

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
PULL FREE POINT @ 100'. PMP 25 SXS CMT @ 2980-2800'. CIRC MUD. SPOT 25 SXS CMT @ 1700-1500'. CIRC MUD. SPOT 25 SXS CMT @ 520-320'. CIRC MUD. BACK OFF 2 JTS 5-1/2" CSG. TOH W/ CSG. SPOT 10 SXS CMT @ 40-3'. CUT OFF AND CAP 8-5/8" CSG 3' BELOW GL.
STATE WITNESS: GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 34151

Address RT 1 BOX 498A, TYRONE, OK 73951-9731 PHONE: (580) 854-6515 12-21-98

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1998

Shirley Childers
Notary Public

My Commission Expires: _____

