

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
100 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21292 -0000

LEASE NAME NUSSER "A"

WELL NUMBER 2

660 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 31 TWP. 34 RGE 41 (E) or (W)

COUNTY MORTON

Date Well Completed 5-31-95

Plugging Commenced 10-02-95

Plugging Completed 10-04-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-01-95 (date)

by STEVE MIDDLETON (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. 5300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1445'	NONE
				5-1/2"	4978'	1994'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

MIRU PUMP TRUCK & CSG PULLERS, PMP 2 SXS HULLS & 25 SXS CMT DWN CSG FROM 4449-4249' OVER PERFS. PULL FREE POINT ON 5-1/2" AND CUT OFF AT 2411' PMPD 35 SXS CMT FROM 2400-2300' PULLED 5-1/2" TO 1475. PMP 35 SXS CMT FROM 1475-1375' PULLED 5-1/2" TO 650' PMPD 35 SXS CMT FROM 650-550' PULL 5-1/2" TO 33' PMPD 10 SXS FROM 33-3' PULL 5-1/2" TO SURF. CUT 8 5/8" OFF 3 FEET BELOW GL. CAP & PERMANENTLY INSCRIBE WELL NAME AND DATE PLUGGED ON CAP. RDMO CASING PULLERS

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGGING

License No. 31151
STATE CORPORATION COMMISSION

Address RT. 1, BOX 49BA, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

RECEIVED
OCT 13 1995

STATE OF KANSAS COUNTY OF SEWARD

CONSERVATION DIVISION
Wichita, Kansas

DAVID W. KAPPLE

(Employee of Operator) or (xxxxxxx) of above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 95



L. Marc Harvey
Notary Public

My Commission Expires: