

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-21,153-0000

LEASE NAME Cyr "A"

WELL NUMBER 1

4030 Ft. from S Section Line

2700 Ft. from E Section Line

SEC. 30 TWP. 34 SRGE. 41 (E) or (W)

COUNTY Morton

Date Well Completed 2/2/93

Plugging Commenced 12/15/94

Plugging Completed 12/18/94

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/18/94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation NA Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 2245

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1414'	3'
				5 1/2	2244'	1555'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU csg pullers. Dug cellar & pit. Mixed 25 sxs hulls & 25 sxs cmt. Spot hulls & cmt from 2130-2000'. Shot 5 1/2" csg off @ 1555'. Pulled to 1440'. Spotted 50 sxs cmt from 1440-1290'. Pulled to 600'. Spotted 40 sxs cmt from 600-500'. Pulled to 40' & spotted 10 sxs cmt from 40-3'. Cut off 8 5/8" csg 3' below gl and capped. Rec 1555' csg. Witnessed by KCC Rep - Glenn Barlow.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sartent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49BA, Tyrone, OK 73951-9731 (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Leslie I. Barnes, Sr. Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes

(Address) Leslie I. Barnes, Sr. Tech. Asst. P.O. Box 351, Liberal, KS 67905-0351

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 11 1995  
1-11-1985  
SUBSCRIBED AND SWORN TO before me this 10th day of January, 1995

CONSERVATION DIVISION  
WICHITA, KS  
Commission Expires: \_\_\_\_\_

CHERYL STEERS  
Notary Public  
My Appt. Expires 6-1-97