

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Finney State Office Building  
 130 South Market, Rm 2078  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-129-21512-0000

LEASE NAME CYR "A"

WELL NUMBER 2

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 30 TWP. 34 RGE 41 (E) or (W)

COUNTY MORTON

Date Well Completed 6-26-97

Plugging Commenced 6-4-98

Plugging Completed 6-8-98

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-3-98 (date)

by MR. GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation CHEROKEE Depth to Top 4416 Bottom 4432 T.D. 4494

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHEROKEE	OIL	4416	4432	8 5/8	1501	NONE
				5 1/2	4552	2317

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MUD PLUGGERS, MIX & PUMP 2 SKS HULLS & 25 SKS CMT FROM 4216-4416'. PULL FREE POINT. CUT OFF 5 1/2" CSG @ 2317'. TOH WITH 5 1/2" CSG TO 1530'. PUMP 50 SKS CMT FROM 1380-1530'. TOH TO 650'. PUMP 40 SKS FROM 550-650'. TOH TO 40' & PUMP 10 SKS FROM 0-40'. CUT OFF AND CAP 8-5/8" 4' BELOW GL. PERMANENTLY INSCRIBE WELL NUMBER AND DATE PLUGGED ON CAP. RDMO PLUGGERS. RESTORE LOCATION. KCC REP. MR. GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 498A, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *L. Marc Harvey 012398*  
 L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 23rd day of July, 1997.

*Freda R. Hinz*  
 Notary Public

My Commission Expires: **FREDAL HINZ**  
 Notary Public - State of Kansas  
 My Appl. Expires 5-15-99