


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County. Sec. 29 Twp. 34S Rge. (E) 41 (W)
Location as "NE/CNW&SW&" or footage from lines Ctr SE NE
Lease Owner Cities Service Oil Company
Lease Name Stewart "D" Well No. 1
Office Address Box 1028, Guymon, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dryhole
Date well completed 8-18 19 64
Application for plugging filed 8-18 19 64
Application for plugging approved 8-19 19 64
Plugging commenced 8-20 19 64
Plugging completed 8-21 19 64
Reason for abandonment of well or producing formation Dryhole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Upper Morrow	Dry	4819	4900	8 5/8"	1437	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 20 sacks of common cement from 4840' to 4914', 20 sacks from 4746' to 4820, 25 sacks from 3183 to 3275, 25 sacks from 2958' to 3050', 35 sacks from 610' to 700' & 15 sacks from 45' to 4' of ground level at which point the 8 5/8" casing was cut off and a steel cap welded on.

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Company
Address Duncan, Oklahoma

STATE OF Oklahoma, COUNTY OF Texas, ss.
H. E. Massey (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. E. Massey *H E Massey*
Box 1028, Guymon, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of September, 19 64

My commission expires 5-4-66

Gloyd L. Shockley
Gloyd L. Shockley Notary Public.