

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS, 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-10329-00-00

LEASE NAME Webb A

WELL NUMBER 5

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

662 Ft. from S Section Line

3307 Ft. from E Section Line

SEC. 28 TWP. 34 RGE. 41 (W) or (X)

COUNTY Morton

Date Well Completed 1-18-61

Plugging Commenced 3-7-02

Plugging Completed 3-11-02

LEASE OPERATOR Oxy USA, Inc

ADDRESS 1701 N. Kansas PO Box 2528 Liberal KS

PHONES (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-6-02 (date)

by Jim Holland (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4951 Bottom 4980 T.D. 5220

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
				8 5/8	1442	-
				5 1/2	5080	1512

RECEIVED
APR 9 5 2002
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each so

Shot 2 3/4 loose @ 4587. Mixed 2 sx hulls & 25 sx cmt to plug parts from 4587 to 4387 & circ. 5 1/2 w/mud. Recover 1512 5 1/2. Circ. hole w/mud 50 sx cmt. 1460 to 1310 40 sx 500 to 380 10 sx 40 to 0. Cut off & cap 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc. 1701 N Kansas PO Box 2528 Liberal, KS

STATE OF Kansas COUNTY OF Seward, ss.


Kenny L. Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1701 N Kansas PO Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 2002

Anita Peterson
Notary Public



Expires: Oct. 1, 2005