

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Morton County, Sec. 27 Twp. 34S Rge. 41 (88) X (W)

Location as "NE/CNW/SW" or footage from lines 100' FSL & 100' FEL of Ctr

Lease Owner Cities Service Oil Company

Lease Name Ward "D" Well No. 1

Office Address Box 1228, Guymon, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 4-13 19 52

Application for plugging filed 8-15 19 69

Application for plugging approved 8-18 19 69

Plugging commenced 9-27 19 69

Plugging completed 10-24 19 69

Reason for abandonment of well or producing formation Uneconomical to produce

If a producing well is abandoned, date of last production 9-26 19 69

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves, Sublette, Kansas

Producing formation Hugoton Depth to top 2256 Bottom 2338 Total Depth of Well 2375 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hugoton	Gas	2338	2256	8 5/8	360	None
				5 1/2	2374	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement plugs were spotted as follows: Spotted 50 sx. cement from 1850' to 2316' (PBTD), mud from 1850' to 882'. Spotted 25 sx. of 50/50 pozmix cement 882' to 667'. Mud from 667' to 90'. Spotted 15 sx. 50/50 pozmix cement 90' to 4' below ground level at which point the 8 5/8" & 5 1/2" casing was cut off and steel cap welded on with date and well name.

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco Well Service

Address 1700 S. Main, Borger, Texas

STATE OF OKLAHOMA, COUNTY OF TEXAS, ss.
H. E. Massey

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. E. Massey
Dist. Manager, Box 1228, Guymon, Oklahoma 73942
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 1969

My commission expires 7-9-73

Melvin E. Dudley
Notary Public

15-129-00418-0000

DRILLERS LOG
Ward "D" #1
Sec. 27-34S-41W
Morton Co., Kansas

Sand & Clay	0 - 126
Sand, Clay, Red Bed	126 - 365
Red Bed & Shale	365 - 400
Shale, Sand, Anhydrite	400 - 970
Anhydrite	970 - 1055
Shale, Sand & Anhydrite	1055- 1290
Shale, Anhydrite	1290 - 1350
Shale, Lime	1350 - 1725
Shale & Gyp	1725 - 2040
Shale & Lime	2040 - 2375
T.D.	2375

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1960
CONSERVATION DIVISION
Wichita, Kansas