

STATE OF KANSAS  
STATE CORPORATION COMMISSION

**Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas**

## WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well. Howard Hess  
Producing formation. \_\_\_\_\_ Depth to top. \_\_\_\_\_ Bottom. \_\_\_\_\_ Total Depth of Well 3553 Feet  
Show depth and thickness of all water, oil and gas formations.

Howard Hess

OIL, GAS OR WATER RECORDS

**CASING RECORD**

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with heavy rotary mud to 225 feet. Bridge at 225 feet with hulls and 20 sacks cement on bridge. Hole filled with heavy rotary mud to 40 feet. Bridge at 40 feet with hulls and 8 sacks cement on bridge. Rat hole capped with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 22 1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor White & Ellis Drilling, Inc. License #209  
Address Box 448, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
Howard E. Russell, employee of Contractor (employee of ~~owner~~ or ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Howard E. Russell

(Signature)

Howard Russell  
Box 448, El Dorado, Kansas

SUBSCRIBED AND SWORN TO before me this 21st day of July 1964  
(Address)

My commission expires September 26, 1964

---

**Notary Public.**

15-191-01557-0000

GP

## Casing Record

8 5/8

405' Cemented  
w/300 sacks

T. D.

3553'

Location: SE SE NW  
 Section: 17-30S-1W  
 Sumner County, Kansas  
 Farm: Volts #3  
 Well Owner: Fred Nixon & White & Ellis  
 Contractor: White & Ellis Drig., Inc.  
 Commenced: 7/8/64  
 Completed: 7/15/64

Kelly Bushing Measurement 5' above ground level.

FORMATION	DEPTH
Soil	0-10
Shale & Lime stks.	310
Lime w/Shale stks.	340
Lime, hd.	405
Lime	485
Lime & Shale stks.	520
Lime & Shale	1030
Shale & Lime stks.	1280
Shale	1370
Shale & Lime	1650
Shale & Shells	1780
Lime	2010
Shale & Lime	2315
Lime	2360
Shale & Lime stks.	2455
Shale	2564
Lime & Shale	2600
Sand	2701
Shale & Lime	2897
Lime	3120
Shale & Lime stks.	3242
Lime & Shale	3275
Lime w/Shale stks.	3379
Shale & Lime	3515
Lime	3553

## TOPS

Kansas City	2896	
B/Kansas City	3124	
Mississippi	3511	
Stainaker Zone	2575	Dry Hole
Stainaker Sand	2612	Plugged & Abandoned

RECEIVED  
STATE CORPORATION COMMISSIONJUL 22 1964  
CONSERVATION DIVISION  
Wichita, Kansas