

15-191-01477-0000

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Sumner County. Sec. 22 Twp. 30S Rge. 1 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NW

Lease Owner PETROLEUM, INC.

Lease Name Henderson Well No. 1

Office Address 100 Derby Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-19 19 49

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 9-19 19 49

Plugging completed 9-19 19 49

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Kans.

Producing formation Depth to top Bottom Total Depth of Well 3960 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	305'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug - 310' - - 15 sacks cement on top of
bottom plug. Filled hole with mud to within 35'
of top. Put in top plug and put 10 sacks cement
on top plug.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to PETROLEUM, INC.
Address 100 Derby Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Eric H. Jager

(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

SEP 21 1949
Eric H. Jager
100 Derby Building, Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of September, 19 49

Raymond Koch
Notary Public.

My commission expires June 7, 1952

22-2625 2-48-15M

PLUGGING
FILE SEC 22 T 30 R 1 W
BOOK PAGE 115 LINE 22

15-191-01477-0000

WELL LOG HENDERSON NO. 1

Petroleum, Inc., Lease Owner.

Section: 22, Twp. 30S, R. 1W

Donald T. Ingling, Contractor

Location: SE SE NW

Rotary Total Depth: 3960'

County: Sumner, Kansas

Commenced: August 23, 1949

Production: Dry

Completed: September 19, 1949

Elevation: 1282 D.F.

Casing: 305' 8 5/8" surface casing

Figures below indicate bottom of formation.

50 Shale
 178 Shale & Shells
 186 Sand
 303 Shale & Shells
 315 Lime
 1430 Shale & Shells
 2240 Lime & Shale
 2295 Lime
 2618 Shale & Lime
 2735 Sand & Shale
 2810 Lime & Shale
 2860 Shale
 2940 Shale & Lime
 3155 Lime
 3450 Lime & Shale
 3517 Shale
 3870 Lime
 3926 Shale
 3960 Sand
 3960 Rotary Total Depth

Tops:

2911 Kansas City
 3524 Mississippian
 3872 Kinderhook
 3926 Simpson Sand

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

Eric H. Jager
 Eric H. Jager

STATE OF KANSAS
 :
 SEDGWICK COUNTY

SS.

PLUGGING
 FILE SEC 22 T 30 R 1W
 BOOK PAGE 115 LINE 22

Subscribed to and sworn to before me, a Notary Public in said County and State this 20th day of September, 1949.

Raymond Koch
 Notary Public

My commission expires: June 7, 1952.