

15-191-01479-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Sumner County, Sec. 22 Twp. 30 Rge. (E) 1 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SE NE NW

Lease Owner. H. M. Williams et al

Lease Name. Henderson Well No. 1

Office Address. 701 Bitting Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed. Feb. 16 19 49

Application for plugging filed. Feb. 17 19 49

Application for plugging approved. Feb. 17 19 49

Plugging commenced. Feb. 17 19 49

Plugging completed. Feb. 17 19 49

Reason for abandonment of well or producing formation. All producing formations dry

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. W. G. Buffington

Producing formation. None Depth to top. Bottom. Total Depth of Well. 3926 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lime		30	315	8 5/8	304	Cemented with 300 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole circulated with heavy mud from 3926 to 290. Hole bridged at 290 and 15 sack cement placed on top of bridge. Heavy mud from on top of cement to 20'. Cement from 20' to 0. cellar floor cemented over and around top of casing

RECEIVED

Conservation Div.

FEB 23 1949

STATE CORPORATION
COMMISSION
KANSAS

2-23-1949

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to H. M. Williams
Address. 701 Bitting Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick part, ss.
H M Williams (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H M Williams

SUBSCRIBED AND SWORN to before me this 23rd day of February 1949

My commission expires Feb 2, 1953 Notary Public.

PLUGGING
FILE SEC 22 Twp 30 R1W
BOOK PAGE 83 LINE 18

15-191-01479-0000

Sullivan Estate, Williams Etal
 Henderson Well No. 1
 Total Depth 3926
 Drilling comm. 1-17-49
 Drilling comp. 2-16-49
 Abandoned 2-17-49

Sec. 22 T. 30 R 1 W
 SE NE NW
 Sumner County, Kansas
 Production Dry
 Elevation 1263
 CASING
 8 5/8" 304' cemented 300 sk

Figures Indicate Bottom of Formations

Soil & shale	30	
lime	315	
lime & shale	1685	
shale	1750	
lime & shale	1890	
lime	1950	
lime & shale	2070	
lime	2220	
lime & shale	2370	
shale	2670	
sand (Stalnaker	2710	
lime & shale	2894	Top K. C. 2894
lime (K. C.)	3130	
lime & shale	3380	
shale	3470	
lime & shale	3501	Top Miss. 3501
lime (Miss.)	3623	
shale	3663	
lime	3711	
lime & shale	3743	
lime	3862	Base Miss. 3862
lime & limy shale	3879	
shale	3886	
hard dolomitic shale	3903	
sand hard	3907	Top Simpson 3903
shaly sand	3926	slight show oil
Total Depth	3926	

Cored 3904 to 19 streaks
 of shale imbedded in sand
 with slight show of oil
 Cored 3919 to 26 with same
 as above

RECEIVED
 Conservation-Div.
 FEB 23 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

PLUGGING
 FILE SEC 22 T. 30 R. 1 W
 BOOK PAGE 83 UNIT 18