


15-191-01018-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Summer County. Sec. 22 Twp. 31 Rge. 1 NE W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE-NE-SW
Lease Owner Petroleum, Incorporated
Lease Name Wille Well No. 1
Office Address 305 East Third, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August 30 19 49
Application for plugging filed October 8 19 52
Application for plugging approved October 13 19 52
Plugging commenced October 13 19 52
Plugging completed October 20 19 52
Reason for abandonment of well or producing formation
Depletion of Producing Zone
If a producing well is abandoned, date of last production September 22 19 52
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington
Producing formation Simpson Depth to top 3,936' Bottom Total Depth of Well 3,941' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	367'	None
				5-1/2"	3,936'	3,172'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand to 3,910'. Filled with 5 sacks cement from 3,910' to 3,875'. Mudded up from 3,875' to 367'. Placed rock bridge from 367' to 340'. Ran 14 sacks cement from 340' to 300'. Mudded up from 300' to 40', and placed rock bridge from 40' to 25'. Capped with 7 sacks cement from 25' to well cellar base.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.,
Address Rural Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.
Paul B. Shivel (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul B. Shivel

RFD #2, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of October, 19 52

My commission expires October 13, 1954

Charlotte Theisman Notary Public.

PLUGGING
FILE SEC 22 T 30 R 12
BOOK PAGE 51 LINE 5

RECEIVED
OCT 29 1952
CONSERVATION DIVISION
Wichita, Kansas

15-191-01018-0000

WELL LOG WILLE No. 1

Petroleum, Inc. - Lease Owner Sec. 22, Twp. 30, Rge 1W
 Donald T. Ingling - Contractor Location: NE SW
 Total Depth: 3944' (rotary) County: Sumner, Kansas
 Commenced: July 5, 1949 Elevation: 1293'
 Completed: August 21, 1949 (rotary) Production: From Simpson
 Casing: 334' 1" of 8 5/8"
 3962' of 5 1/2"

Figures below indicate bottom of formation:

40 Clay Shale	2925 Shale and Lime		
315 Shale and Shells	3250 Lime		
330 Lime	3531 Lime and Shale		
350 Shale and Shells	3552 Lime Chat		
380 Shale	3560 Lime		
2590 Lime and Shale	3585 Lime Hard		<u>Tons</u>
2690 Lime and Sand	3590 Lime	2924	Kansas City
2730 Sand	3610 Lime Hard	3540	Mississippi
2785 Shale and Lime	3870 Lime	3585	Kinderhook
2809 Shale	3944 TOTAL DEPTH	3936	Simpson

I hereby certify that this is a true and correct log of the above mentioned well.

STATE OF KANSAS
SEDGWICK COUNTY

SS:

DONALD T. INGLING
 RECEIVED
 STATE CORPORATION COMMISSION
 AUG 22 1949
 CONSERVATION DIVISION
 Wichita, Kansas
M. E. Black

PLUGGING
 FILE SEC 22 T 30 R 12
 BOOK PAGE 51 LINE 5

Subscribed and sworn to before me, a Notary Public in said County and State on this day, the 22nd day of August, 1949.

Mary Hanna
 Notary Public

My commission expires: 10/22-49