


15-191-10177-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

SUMNER County. Sec. 22 Twp. 30S Rge. 1W (E) (W)



Location as "NE/CNW/SW" or footage from lines SW 1/4 SW 1/4 NE 1/4
Lease Owner Thomas E. Sullivan and others
Lease Name NIXON Well No. 4
Office Address 218 Plaza Theatre Bldg., Kansas City 12, Missouri
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed August 17 19 49
Application for plugging filed October 29 19 57
Application for plugging approved November 1 19 57
Plugging commenced December 13 19 57
Plugging completed December 24 19 57
Reason for abandonment of well or producing formation
It ceased production.

If a producing well is abandoned, date of last production August 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham
Producing formation Simpson Depth to top 3915 Bottom 3925 Total Depth of Well 3925 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Simpson	Water	3925	3600	5 1/2"	3900	3137

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5 sax cement in bottom of hole, came up 240 ft., and put rock bridge in.
15 sax cement on top of rock bridge. Filled up with mud within 50 ft. of top; then another rock bridge; then put in another 10 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1958
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor RED TOP DRILLING COMPANY (If additional description necessary, use BACK of this sheet)
Address WINFIELD, KANSAS

STATE OF Missouri COUNTY OF Jackson, ss.
THOMAS E. SULLIVAN (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas E. Sullivan
218 Plaza Theatre Bldg., Kansas City 12, Missouri

SUBSCRIBED AND SWORN TO before me this 15th day of JANUARY, 19 58
My commission expires January 18, 1961
Notary Public

PLUGGING
FILE SEC 22 T 30 R 1 W
BOOK PAGE 58 LINE 25

15-191-10177-0000

Sullivan Estate Et Al
Nixon Well No. 4

Sec. 22 T. 30 N. R. 1 W

SW SW NE
Sumner County, Kansas

Total Depth
Drilling comm 7-26-49
Drilling comp. 8-17-49

Production
Elevation 1285 (derrick floor)
Casing
8 5/8 317' (300 sk cement)
5 1/2 (123) 3913' (130 " ")

Figures Indicate Bottom of Formations

Soil & shale	240	
rock	254	
shale & shells	295	
shells & lime	317	
shale & lime	385	
lime broken	585	
shale & lime shells	1125	
shale, lime & brown rock	1470	
shale	1681	
shale & shells	1890	
lime & shale	2150	
lime broken	2225	
lime	2330	
lime & shale	2425	
lime broken	2485	
lime & shale	2622	
shale	2645	
sand	2696	
shale	2713	
lime & shale	2905	Top Kansas City line 2900
lime	3120	
lime broken	3153	
lime	3213	
lime & shale	3250	
lime	3279	
lime & shale	3347	
shale	3398	
lime broken	3446	
shale	3501	Top Miss. line 3501
Line (Miss)	3875	Base Miss. line 3875
shale Kinderhook)	3913	Top Simpson Sand 3913
sand Simpson	3925	lost circ. at 3914
Total Depth with rotary	3925	

Well completed with cable tools. Plug drilled 8-20-49 and started flowing 50 bbls per hour

PLUGGING
FILE SEC. 22 T. 30 R. 1 W.
BOOK PAGE 58 LINE 25