


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

SUMNER County. Sec. 22 Twp. 30s Rge. 1w (E) (W)



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Thomas E. Sullivan et al
Lease Name NIXON
Office Address 218 Plaza Theatre Bldg., Kansas City 12, Missouri
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 6-19-44
Application for plugging filed November 19 58
Application for plugging approved November 9 19 58
Plugging commenced November 9 19 58
Plugging completed November 12 19 58
Reason for abandonment of well or producing formation
Ceased to Produce Oil.

If a producing well is abandoned, date of last production 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eugene Graham
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3917 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,082.23

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

25 gal chat on bottom
5 sacks cement
Mud to 230'
Set bridge at 230'
15 sacks cement on bridge
Mud to 25'
6 sacks cement on top

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF MISSOURI COUNTY OF JACKSON, ss.
THOMAS E. SULLIVAN (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas E. Sullivan
218 Plaza Theatre Bldg., Kansas City 12, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1958

My commission expires January 18, 1961
Notary Public.

PLUGGING
FILE SEC 22 T. 30 R. 1W
BOOK PAGE 143 LINE 25

WELL RECORD

M. J. SULLIVAN ET AL
Nixon No. 1
Total Depth 3929
Comm. 5-3-1944 Comp. 6-12-1944
Comp. with cable tools 6-19-1944
Contractor H. M. Williams

SEC. 22 T. 30 S R. 1 W
C NE NE
SUMNER County
ELEVATION 1276
PRODUCTION POTENTIAL 209 bbls
GRAVITY 45 NO WATER

State Potential 8-1-1944

CASING
10 3/4" 225'
8 5/8" 385'
5 1/2" 3916'
TUBING
2 1/2" Upset 3923'(126 jts)

Figures Indicate Bottom of Formations

Cellar	6
shale	227
lime & shale	450
shale & lime shells	645
lime & shale	815
lime	920
lime & shale	1300
shale & shells	1490
lime & shale	1965
lime	2225
lime & shale	2685
lime	2710
lime hard	2745
lime & shale	2896 Top Kansas City 2896
lime	2918
lime soft porous	2926
lime	2971
lime soft porous	2980
lime	2985
lime soft	2990
lime	3001
lime soft porous, show oil	3006
lime	3072
lime & shale	3293
lime	3323
lime & shale	3427
lime	3452
lime & shale	3505
chat & lime	3515 Top Mississippi 3505
lime	3655
chatty lime	3676
lime hard	3804
lime soft	3811
lime	3877 Base Mississippi 3877
shale black	3917
Simpson sand	3929 Top Simpson 3917
Total Depth	3929

Cored 3915 to 3925, 8 feet
fill saturation.
Drilled with cable tools
3925 to 3929 with good oil
saturation

Well had fill up of 3000'
and flowed an estimated
100 bbls. Gravity of oil
when completed was 43 and
has now increased to 45

RECEIVED
MISSOURI COMMISSION

NOV 7 1958

CONSERVATION DIVISION
Wichita

PLUGGING
FILE SEC. 22 T. 30 S. R. 1 W.
BOOK PAGE 143 LINE 25