

15-191-01476 0000

# WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR

## FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Sumner County. Sec. 22 Twp. 30 Rge. 1 (E) (W)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW SE  
 Lease Owner PETROLEUM, INC.  
 Lease Name Hurst Well No. 3  
 Office Address 100 Derby Building, Wichita 2, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed January 2, 19 50  
 Application for plugging filed January 20, 19 50  
 Application for plugging approved January 4, 19 50  
 Plugging commenced January 2, 19 50  
 Plugging completed January 2, 19 50  
 Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Buffington  
 Producing formation Depth to top Bottom Total Depth of Well 3922 Feet  
 Show depth and thickness of all water, oil and gas formations.

### OIL, GAS OR WATER RECORDS

### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 1/8"	319'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 319', set plug at 319' and cemented with 15 sacks of cement. filled hole with heavy mud and 10 sacks of cement on top to bottom of cellar. Surface casing cut off and cellar filled with surface soil.

RECORDED  
 1-23-1950  
 JAN 23 1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to PETROLEUM, INC.  
 Address 100 Serby Building Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
 Eric H. Jager (employee of owner) or (owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager  
 Exec. Vice-President  
 100 Derby Building, Wichita 2, Kansas  
 (Address)

SUBSCRIBED AND SWORN to before me this 20th day of January, 19 50.  
 Marjorie Bradshaw  
 Notary Public.

My commission expires October 27, 1952

PLUGGING  
 FILE SEC 22 T 30 R 16  
 BOOK PAGE 137 LINE 16

WELL LOG HURST NO. 3

Petroleum, Inc., Lease Owner  
Melland Drilling Co., Contractor  
Rotary Total Depth: 3922'  
Commenced: December 10, 1949  
Completed: January 2, 1950  
Casing: 319' of 8 5/8"

Section 22, Twp. 30S, Rge. 1W  
Location: NW SW SE  
County: Sumner, Kansas  
Production:  
Elevation:

Figures below indicate bottom of formation:

140	Surface Clay	2760	Shale & Lime
220	Shale & Shells	2995	Lime
245	Shale & Lime	3529	Shale & Lime
260	Lime	3565	Chat. Lime
275	Salt	3610	Lime
288	Shale	3682	Lime Rough
290	Lime hard	3697	Lime
319	Lime	3905	Lime & Shale
341	Lime	3908	Shale
355	Lime & Shale	3922	Sand
295	Shale & Shells		
470	Lime broken	3922	R.T.D.
605	Shale & Lime		
820	Shale & Shells		
930	Red Bed		
945	Lime & Shale		
1050	Red Rock		
1130	Shale & Shells		
1295	Shale & Lime		
1746	Shale & Shells		
2055	Lime & Shale		
2165	Lime		
2510	Shale & Lime		
2555	Lime		
2694	Sandy shale & sand		
2710	Shale		

Tons

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

**PLUGGING**  
FILE SEC 27-30-R24  
BOOK PAGE 137 LINE 16

*Eric H. Jager*  
Eric H. Jager  
Notary Public

STATE OF KANSAS :  
: SS. SEDGWICK COUNTY :

JAN 23 1950

Subscribed to and sworn to before me, a Notary Public in said County and State this 11th day of January, 1950.

*Marjorie Bradshaw*  
Notary Public

My commission expires: Oct. 27, 1952.