


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sumner County, Sec. 22 Twp. 30 Rge. 1 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. NW NW SE
Lease Owner Petroleum, Inc.
Lease Name Hurst Well No. 1
Office Address 100 Derby Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 23, 1949
Application for plugging filed November 23, 1951
Application for plugging approved November 23, 1951
Plugging commenced November 23, 1951
Plugging completed November 30, 1951
Reason for abandonment of well or producing formation
Production Depleted
If a producing well is abandoned, date of last production October 1951
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Buffington
Producing formation Simpson Sand Depth to top 3918 Bottom Total Depth of Well 3933 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	308'	None
				5 1/2"	3920'	3021'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with rock to 3920' and cemented to 3890'. Filled hole with mud to 310' and filled with rock to 300'. Cemented with 15 sax cement from 300' to 250' and filled with mud to 30'. Cemented with 10 sax cement to cellar.

DEC 7 1951
DIVISION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.
Address 100 Derby Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Eric H. Jager (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
100 Derby Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1951.

My commission expires October 13, 1954

Notary Public.

FILE NO. 271 30-110
229-113

WELL LOG - HURST NO. 1

Petroleum, Inc. - Lease Owner

Sec. 22, Twp. 30S, Range 1W

Donald T. Ingling - Contractor

Location: C NW NW SE

Total Depth: 3933' (rotary)

County: Sumner, Kansas

Commenced: June 5, 1949

Elevation: 1202'

Completed: July 3, 1949 (rotary)

Production:

Casing: 309' of 8-5/8"
3920' of 5 1/2"

Figures below indicate bottom of formation:

175 Limestone and Shale	<u>Tops</u>	2705 Sand & Shale
183 Sand		2820 Shale & Lime
193 Shale & Lime	Kansas	2900 Shale
303 Shale & Shells	City 2908(-1624)	2960 Shale & Lime
308 Lime	Mississi-	3140 Lime
1290 Shale & Lime	ppian 3527(-2243)	3435 Lime & Shale
1305 Sand	Simpson	3527 Shale
1420 Shale & Lime	Sand 3918(-2634)	3529 Cherty Lime
1585 Shale	Total	3545 Shale & Lime
2095 Lime & Shale	Depth 3933(-2649)	3805 Lime
2130 Sand & Shale		3918 Sand
2195 Sandy Lime & Shale		3923-3928 Sand & Lime
2610 Lime & Shale		3928-3933 Sand & Shale
		3933' Total Depth.

I hereby certify that this is a true and correct log of the above mentioned well.

STATE OF KANSAS
S. S.
Sedgwick County

RECORDED
DONALD T. INGLING
DEC - 7 1951
COMMISSIONER OF REVENUE
Topeka, Kansas

M. E. Black

Subscribed and sworn to before me, a Notary Public in said County and State on this day, the 5th day of July, 1949.

FLUORINE
FILE NO. 22130-R(W)

Mary Hanna
Notary Public

My Commission Expires: October 22, 1949.