


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Sumner County, Sec. 24 Twp. 30S Rge. 1 (W)
Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Franco Central Oil Company
Lease Name Parker Well No. 1
Office Address Fourth National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed December 23 19 56
Application for plugging filed December 23 19 56
Application for plugging approved December 23 19 56
Plugging commenced December 23 19 56
Plugging completed December 23 19 56
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. G. Buffington
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253 1/2'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud to 250 ft.
Halliburton plug at 250 feet with 15 sacks cement
on bridge. Hole filled with heavy rotary mud to 35
ft. Halliburton plug at 35 feet with 10 sacks cement
from plug to surface.

RECEIVED
STATE CORPORATION COMMISSION
1-17-1957
JAN 17 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc., License #209
Address Box 148, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Bruce Auer

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce Auer
Box 148, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of December, 19 56

My Commission Expires April 14, 1958
My commission expires _____

Dale R. Daniel
Notary Public.

PLUGGING
FILE SEC 24 T. 30 R. 1 W
BOOK PAGE 128 LINE 40

Casing Record
 8 5/8 253 1/2' cemented
 w/250 sacks
 T.D. 3900 feet

Location: NW/4 - NW/4 - SW/4
 Sec. 24 - 30S - 1W
 Summer County, Kansas
 Farm: Parker # 1
 Well Owner: Franco Central Oil Company
 Contractor: White & Ellis Drilling, Inc.
 Started: 12/10/56
 Completed: 12/23/56

Kelly bushing measurements 5' above ground level.

<u>FORMATION</u>	<u>DEPTH</u> - Figures indicate bottom of formation.
Sandy shale	0 - 100
Shale	233
Lime & Shale	830
Shale	960
Lime & Shale	1170
Shale & Shell	1490
Lime	1530
Shale & Lime	1710
Lime & Shale	1790
Lime	1886
Lime w/ shale strks.	2075
Lime	2280
Lime & shale	2305
Lime	2310
Shale & Shell	2525
Lime	2535
Sand	2575
Sand & Sandy Shale	2615
Shell & Shale strks.	2785
Shale	2854
Lime	2929
Top of Kansas City	
Lime	3132
Shale & Lime	3465
Top of Mississippi	
Lime	3828
Shale & Lime	3858
Top of Simpson	
Sand	3900

3

Dry hole plug & abandon

PLUGGING	
FILE SEC.	24 T. 30 R. 1W
BOOK PAGE	128 LINE 40

RECEIVED
 STATE CORPORATION COMMISSION

JAN 17 1957

CONSERVATION DIVISION
 Wichita, Kansas