

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-191-21,682-0000

LEASE NAME Turney

WELL NUMBER #1

SPOT LOCATION C W/2 NE NW

SEC. 24 TWP. 30S RGE. 1 (E/W) (W)

COUNTY Sumner

Date Well Completed 6-16-84

Plugging Commenced 6-16-84

Plugging Completed 6-16-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Raymond Oil Co., Inc.

ADDRESS One Main Place - Suite 900 Wichita, Ks. 67202

PHONE # (316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 2

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom T.D. 3871'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	302'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Fill hole w/mud to surf.

Spotted 35 sx. cement @ 1250' thru drill pipe.

Spotted 35 sx. cement @ 340' thru drill pipe.

Spotted plug @ 60' w/20 sx. cement thru drill pipe.

Spotted 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernest Sifford

(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1984


David F. Jamis
Notary Public
David F. Jamis.


RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1984

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires:





WHITE

ANDELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Raymond Oil Co., Inc. One Main Place - Suite 900 Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Turney Well No. 1

Sec. 24 T. 30S R. 1W Spot C W/2 NE NW

County Sumner State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 302' with 125 SX. 3% cc

Production: @ with SX.

Type Well: D & A Total Depth 3871'

Drilling Commenced 6-7-84 Drilling Completed 6-16-84

Formation	From	To	Tops	
Cellar	0	7	Iatan	2504
Shale, Sand	7	1711	Stalnaker	2518
Shale, Lime, Sand	1711	1880	Kansas City	2833
Shale, Lime	1880	2504	Mississippi	3439
Lime	2504	2518	Kinderhook	3819
Sand	2518	2598	Simpson	3869
Shale	2598	2833		
Lime	2833	3024		
Lime, Shale	3024	3075		
Shale, Lime	3075	3117		
Lime, Shale	3117	3439		
Lime	3439	3746		
Lime, Shale	3746	3819		
Shale	3819	3869		
Sand	3869	3871		

JUN 28 1984

CONSERVATION DIVISION
Wichita, Kansas