

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-191-20262-0000

API NUMBER 4-3-1971

LEASE NAME spexarth

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

610 Ft. from S Section Line

3250 Ft. from E Section Line

SEC. 21 TWP. 30S RGE. 3W (E) or (W)

COUNTY Sumner

Date Well Completed 4-10-71

Plugging Commenced 10-3-1995

Plugging Completed 10-6-95

LEASE OPERATOR VAL Energy Inc.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE (316) 522-1560 OPERATORS LICENSE NO. 5822

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-2-1995 (date)

by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filled? ? If not, is well log attached? yes

Producing Formation simpson Depth to Top 4271 Bottom 4340 T.D. 4340

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	253	8 5/8	253	none
		0	4340	4 1/2	4340	2650

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Casing leak, mud to 2900 ft. set 4 1/2 CIBP at 2920, dump 2 sx cement

on top of plug, shoot pipe at 2650, spot 35sx cement plug at 700 ft,

circulate from 300 ft. to surface with cement.

Allied Cementing, # 2069

Name of Plugging Contractor VAL Energy, Inc.

License No. 5822

Address Box 322 Haysville, Ks. 67060

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: VAL Energy Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

OCT 11 1995

10-11-1995

CONSERVATION DIVISION

Todd Allam

(Employee of Operator Wichita, Kansas)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Todd Allam

(Address) Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 10th day of October, 19 95

Gary D. Stearns
Notary Public

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM



Form CP-4
Revised 05-88

