

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

-API NUMBER 15-191-20,264-0000

LEASE NAME Spexarth

WELL NUMBER #2

TYPE OR PRINT
NOTICE: Fill out complotely
and return to Cons. Div.
office within 30 days.

1830 Ft. from S Section Line

3300 Ft. from E Section Line

LEASE OPERATOR Jay Boy Oil, Inc.

SEC. 21 TWP 30 RGE. 3 (E) or (W)

ADDRESS 224 E. Douglas, Suite 425, Wichita, Ks. 67202

COUNTY Sumner

PHONE# (316)-264-3700 OPERATORS LICENSE NO. 4569

Date Well Completed _____

Character of Well Oil

Plugging Commenced 4-13-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-18-90

The plugging proposal was approved on April 18, 1990 (date)

by Steve Van. Giesen (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4330'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	249'	None
				4-1/2"	4330'	2,630.42'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet, each set. Dumped sand to 3780' and 4 sacks cement. Shot casing at 3409', 3116', 2821' & 2662'. Pulled 83 joints of 4-1/2" casing. Halliburton plugged well with 35 sacks cement at 1000', 35 sacks cement at 700' and 60 sacks cement at 300' circulated to surface

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jay Boy Oil, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Kansas 67530

STATE OF KANSAS
5-9-1990
MAY 09 1990
CONSERVATION DIV.
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 8th day of May, 19 90.

My Commission Expires _____

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-16-91

James M. Leatherman
Notary Public