

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15,191-20,279-0000

LEASE NAME Cecil

WELL NUMBER #1

3150 Ft. from S Section Line

2130 Ft. from E Section Line

SEC. 21 TWP. 30 RGE. 3 (E) or (W)

COUNTY Sumner

Date Well Completed _____

Plugging Commenced 4-23-90

Plugging Completed 5-7-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Jay Boy Oil, Inc.

ADDRESS 224 E. Douglas, Suite 425, Wichita, Ks. 67202

PHONE# (316)-264-3700 OPERATORS LICENSE NO. 4569

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 7, 1990 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 4314'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS:

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	234'	None
				4-1/2"	4312;	27,15.53'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4200' and 4 sacks cement. Shot casing at 3509', 3241', 2980' and 2751'. Pulled 87 joints of 4-1/2" casing. Howco plugged well with 35 sacks cement at 1000' 35 sacks cement at 700', cement circulated to surface from 300' and squeezed with 50 sacks cement.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jay Boy Oil, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORA
 5-17-1990
 MAY 17 1990

(Signature) James W. Rockhold

(Address) James W. Rockhold

Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 16th day of May, 19 90
 WICHITA, KANSAS

Jona M. Leatherman
 Notary Public

My Commission Expires:

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91