

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 5 Twp. 30S Rge. (E) 6 (W)

Location as "NE/CNW/SE/SW" or footage from lines. C SW SW

Lease Owner: Rains & Williamson Oil Co., Inc.

Lease Name: CESSNA Well No. 1

Office Address: 1425 Wichita Plaza - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-31 19 68

Application for plugging filed 7-31 19 68

Application for plugging approved 7-31 19 68

Plugging commenced 7-31 19 68

Plugging completed 3:15 PM 7-31 19 68

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production -- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren, Pratt, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 4132 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	292'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud back to 285'. Set plug, 1/2 sacks hulls and 25 sacks cement.
Mud back to 40'. Set solid bridge and capped with 10 sacks; 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Rains & Williamson Oil Co., Inc.
Address: as above


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6 day of August, 19 68

June 30, 1971

Sherry Gish
Notary Public.



ROTARY DRILLING LOG

Operator: Rains & Williamson
 Oil Co., Inc.
 CESSNA #1
 C SW SW 5-30S-6W
 Kingman County, Kansas

Contractor: Rains & Williamson
 Oil Co., Inc.
 Commenced: 7-22-68
 Completed: 7-31-68
 Remarks: 8-5/8" @ 292'/215 sx.

Formations

Sand	35'
Shale	1050'
Lime and Shale	1750'
Shale and Lime	2630'
Lime and Shale	3620'
Lime	3690'
Lime and Shale	3815'
Lime	3925'
Lime and Shale	4080'
Lime and Chert	4132'
 Rotary Total Depth (D & A)	 <u>4132'</u>


RECEIVED
 STATE CORPORATION COMMISSION
 AUG 7 1968
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

Wilson Rains

 Wilson Rains



Subscribed and sworn to before me, a Notary Public within and for the State of Kansas, County of Sedgwick, this 6th day of August, 1968.

Sherry Gish

 Sherry Gish Notary Public

My Commission Expires:
 June 30, 1971