

15-095-21336-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. _____ TWP. _____ RGE. _____ E/W _____
Location as in quarters or footage from lines:
990' FNL; 1650' FWL in NW/4

Lease Owner F. G. Holl
Lease Name Cessna #1-5 Well No. 1-5
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): XX
Date Well Completed May 4, 1983
Application for plugging filed May 4, 1983
Plugging commenced 10:30 AM, May 4, 1983
Plugging completed 12:00 Noon, May 4, 1983
Reason for abandonment of well or producing formation Dry Hole

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Van Gieson

Producing formation _____ Depth to top _____ bottom T.D. 4300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	262'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Plugged through open ended drill pipe.
Circulated 35 sacks at 300'; 25 sacks
at 60'; 10 sacks in rathole. Used
50/50 Pozmix plus 2% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 83

Agnes D. Wurst
Notary Public.

My Commission expires: 4-6-85

RECEIVED STATE CORPORATION COMMISSION

MAY 09 1983

MAY 09 1983

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- CESSNA #1-5

Located: 990' FNL; 1650' FWL in NW/4, Section 5-30S-6W,
Kingman County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 25, 1983

COMPLETED: May 4, 1983

TOTAL DEPTH: 4300'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 30 Surface Soil and Gravel	Ran 6 joints new 8 5/8", 24# casing. 249.80' pipe set at 262' K.B.
30 - 265 Red Rock and Shale	Cemented with 200 sacks 60/40 Pozmix plug 3% cc. Plug down at 10:30 PM, 4-25-83, by Howco.
265 - 1021 Shale	
1021 - 4160 Lime and Shale	
4160 - 4300 Chert Lime	Plugged.

Deviation Surveys: 1 3/4° at 1545'
 1/8° at 2040'
 1° at 2384'
 1 1/2° at 3750'
 1 1/2° at 4160'
 1 1/4° at 4300'

RECEIVED
 STATE CORPORATION COMMISSION

MAY 09 1983

CONSERVATION DIVISION
 Wichita, Kansas