


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 5 Twp. 30S Rge. 6 (X) (W)
Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Stelbar Oil Corporation, Inc.
Lease Name Cessna Well No. 1
Office Address 310 Petroleum Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 19, 19 63
Application for plugging filed May 19, 19 63
Application for plugging approved May 19, 19 63
Plugging commenced May 19, 19 63
Plugging completed May 19, 19 63
Reason for abandonment of well or producing formation Dry



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Howard Hess
Producing formation Depth to top Bottom Total Depth of Well 4115 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	195	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole with mud to 225'. Set plug, ran 1/4 sack hulls and 20 sacks cement, mud to 40'. Set plug and ran 1/4 sack hulls and 8 sacks of cement. Ran 2 sacks cement in rat hole.


RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stelbar Oil Corporation, Inc.
Address 310 Petroleum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bertrand M. Lester, Jr. (employee of owner) or ~~(owner)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Bertrand M. Lester Jr*
310 Petroleum Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 19 63
My commission expires May 7, 1966.
Talia Zuhars
Talia Zuhars Notary Public.



LOG

Farm: Cessna
Well No. 1
C SW SE Sec. 15-30S-6W
Kingman County, Kansas

Owner: Stelbar Oil Corporation, Inc.
Contractor: Stelbar Oil Corporation, Inc.
Drilling commenced: 5-6-63
Drilling Completed: 5-19-63

Elevation: 1426 KB
1423 DF
1421 GL

8-5/8" Casing set at 195' W/ 185 Sacks

	From	To
Sand & Gravel	0	27
Bro. Lime	27	110
Shale & Shells	110	975
Lime	975	1420
Shale	1420	1465
Lime	1465	1575
Shale & Shells	1575	1635
Lime	1635	1707
Shale & Shells	1707	1970
Shale & Sandy Lime	1970	2000
Shale & Lime	2000	2080
Shale & Shells	2080	2245
Shale & Lime	2245	2795
Lime	2795	2870
Lime & Shale	2870	2997
Shale & Sandy Lime	2997	3090
Lime & Shale	3090	3239
Lansing Lime	3239	3402
Shale & Lime	3402	3513
K. C. Lime	3513	3725
Lime	3725	3776
Lime & Shale	3776	4069
Miss. Lime	4069	4105
Miss. (Chert)	4105	4115
Rotary Total Depth	4115	

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1963

CONSERVATION DIVISION
Wichita, Kansas

Plugged hole with mud to 225'. Set plug, ran 1/4 sack hulls and 20 sacks cement, mud to 40'. Set plug and ran 1/4 sack hulls and 8 sacks of cement. Ran 2 sacks cement in rat hole.