


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Kingman County. Sec. 13 Twp. 30S Rge. (E) 6 (W)
Location as "NE/CNW%SW%" or footage from lines SE SW SE
Lease Owner Stelbar Oil Corporation, Inc.
Lease Name Van Dorien Well No. 1
Office Address 310 Petroleum Building
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed April 13, 1960
Application for plugging filed May 17, 1960
Application for plugging approved May 17, 1960
Plugging commenced May 17, 1960
Plugging completed May 17, 1960
Reason for abandonment of well or producing formation dry hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4583 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back from 4583 to 3630, plug set at 3630'; filled with cement from 3630' to 3574' (7 sacks cement); filled with mud from 3574 to 240; filled with rock from 240' to 230'; filled with cement from 230' to 185' (15 sacks); filled with mud from 185' to 35'; filled with rock from 35' to 25'; filled with cement from 25' to 0 (10 sacks)

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R. L. Patterson and Son
Address P.O. Box 201, Arkansas City, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bertrand M. Lester, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bertrand M. Lester, Jr.
310 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of May, 1960

My commission expires January 18, 1964
Leona Stangor Notary Public.



LOG

Farm: Van Dorien
Well No. 1
SE SW SE 13-30S-6W
Kingman County, Kansas

Owner: Stelbar Oil Corporation, Inc.
Contractor: Stelbar Oil Corporation, Inc.
Drilling Commenced: 3-24-60
Drilling Completed: 4-13-60

8-5/8" 251' cemented with 200 sacks
5-1/2" 3724' cemented with 80 sacks

Elevation: 1385 DF
1383 GR

0	70	Surface clay, sand	4-28-60	Perforate 3643 to 3649,
70	250	Broken Lime		4 shots per ft.
250	1405	Shale and Shells		Mud acid, 500 gal.
1405	1535	Shale and Lime	4-29-60	Fill-up 1000' overnight
1535	1595	Shale and Shells		Swabbed 8 bbls. oil, 40 bbls.
1595	1650	Shale and Lime		water in 6 hrs. Swabbed 2
1650	2600	Shale and Shells		bbls. fluid per hour for 2 hrs.
2600	2675	Shale and Lime	5-1-60	Gave 2,000 gal. acid, swabbing
2675	2913	Lime		load back.
2913	3021	Lime and Shale	5-2-60	Swabbed load back, swabbed 30
3021	3298	Lime		bbls. fluid per hr., 10% oil 400'
3298	3350	Sandy Shale		off bottom.
3350	3400	Sandy Lime & Shale	5-2-60	Set plug at 3630'. Perforated
3400	3505	Lime and Shale		3613 to 3620. Swabbed hole down,
3505	3730	Kansas City Lime		filled up 300', 30' oil in 1 1/2
3730	4062	Lime and Shale		hrs. Testing.
4062	4092	Shale	5-3-60	Filled up 800' in 11 hrs. (17 bbls.
4092	4337	Mississippi Lime		water, 3 bbls. oil).
4337	4461	Lime		Swabbed 2 1/4 bbls. water and
4461	4522	Shale		1/4 bbl. oil per hr. for 2 hrs.
4522	4530	Viola Lime		
4530	4553	Lime		
4553	4583	Simpson Sand		
	4583	RTD		