


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 15 Twp. 30S Rge. 6W (E) (W)
Location as "NE/CNW/SW" or footage from lines App. C NE SW
Lease Owner Walters Drilling Co. et al
Lease Name Dewey "A" Well No. 1
Office Address 510 Orpheum Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-30-65 19
Application for plugging filed 7-30-65 19
Application for plugging approved 7-30-65 19
Plugging commenced 7-30-65 19
Plugging completed 7-30-65 19
Reason for abandonment of well or producing formation commercial quantities of oil not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well A. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4520 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 226 | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 225' w/ 25 sacks cement
Top Plug @ 40' w/ 10 sacks cement
2 sacks rat hole

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Walters Drilling Co.
Address 510 Orpheum Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert F. Walters (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Robert F. Walters
510 Orpheum Building, Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of August, 19 65
My commission expires October 4, 1967
Juanita M. Green Notary Public.



DRILLER'S LOG

COMPANY: WALTERS DRILLING CO. ET AL
510 ORPHEUM BUILDING
WICHITA, KANSAS 67202

WELL NAME: DEWEY "A" #1
APP. C NE SW SECTION 15-30S-6W
KINGMAN COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
510 ORPHEUM BUILDING
WICHITA, KANSAS 67202

ROTARY DRILLING COMMENCED: JULY 20, 1965
ROTARY DRILLING COMPLETED: JULY 30, 1965

ELEVATION: 1393 KB

CASING RECORD: 8 5/8" @ 226' w/ 190 sks.

LOG

| | |
|-------------|---------------------------------------|
| 0 - 30 | Sand |
| 30 - 226 | Shale and Red Rock |
| 226 - 950 | Shale |
| 950 - 1105 | Shale and Shells |
| 1105 - 2205 | Shale and Lime |
| 2205 - 2395 | Shale |
| 2395 - 2855 | Shale and Lime |
| 2855 - 3125 | Shale |
| 3125 - 3248 | Shale and Sand |
| 3248 - 3560 | Lime and Shale |
| 3560 - 3615 | Lime |
| 3615 - 3725 | Lime |
| 3725 - 4105 | Lime and Shale |
| 4105 - 4270 | Lime and Chert |
| 4270 - 4341 | Lime |
| 4341 - 4367 | Lime and Chert |
| 4367 - 4455 | Shale and Lime |
| 4455 - 4484 | Lime and Shale |
| 4484 - 4494 | Dolomite and Sand |
| 4494 - 4520 | Sand |
| <u>4520</u> | <u>Rotary Total Depth - D & A</u> |


The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY


 ROBERT F. WALTERS, Partner

Subscribed and sworn to before me
this 4th day of August, 1965


 Juanita M. Green, Notary Public

My Commission Expires: October 4, 1967

RECEIVED
 STATE CORPORATION COMMISSION

AUG 13 1965

CONSERVATION DIVISION
 Wichita, Kansas