


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-1

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Kingman County, Sec 6 Twp 29S Rgc (X) 5 (W)
Location as "NE/CNW4SW4" or footage from lines SW NW NE
Lease Owner Graves Drilling Co., Inc.
Lease Name Eleanor Well No. 1
Office Address 910 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 11, 1975
Application for plugging filed June 11, 1975
Application for plugging approved June 11, 1975
Plugging commenced June 11, 1975
Plugging completed June 11, 1975
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3970 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	207'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 175 feet. Followed by wooden plug and 1/2 sack hulls
Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed
by wooden plug, 1/2 sacks hulls and 10 sacks cement to base of well cellar.
Plugged rat hole with 2 sacks cement.

JUN 16 1975
6-16-75

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 910 Union Center, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss.

John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
910 Union Center, Wichita, Kansas 67202 (Address)

Subscribed and sworn to before me this 13 day of June 1975

My commission expires May 9, 1979 Betty Brandt Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: June 4, 1975

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: June 11, 1975

CASING RECORD: 6 Jts. 207' of 8-5/8"
cemented with 175 sacks

LOCATION: Eleanor No. 1
SW NW NE
Section 6-29S-5W
Kingman County, Kansas

0 - 208	10' sand on top, red bed & shale
208 - 255	Shale
255 - 830	Shale, shells & sand streaks
830 - 1100	Lime & shale streaks
1100 - 1407	Lime & shale streaks
1407 - 1730	Shale & lime
1730 - 2325	Lime & shale streak
2325 - 2790	Lime & shale
2790 - 3225	Shale with lime streaks
3225 - 3288	Shale
3288 - 3302	Shale & lime
3302 - 3512	Lime & shale
3512 - 3836	Lime
3836 - 3843	Lime & shale
3843 - 3970	Chert & dolomite
3970	Rotary Total Depth

JUN 16 1975

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 13th day of June, 1975

My commission expires: May 9, 1979

Betty Brandt
Betty Brandt Notary Public