


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Kingman County, Sec. 6 Twp. 29S Rge. 5W (E)(W)

Location as "NE/CNW/SW" or footage from lines SE NW NW

Lease Owner Stelbar Oil Corporation, Inc.

Lease Name Kosner B Well No. 1

Office Address 310 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 5-25-61 19

Application for plugging filed May 25, 1961

Application for plugging approved May 25, 1961

Plugging commenced May 25, 1961

Plugging completed May 25, 1961

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3986 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with mud to 240', set plug, dumped 20 sacks cement; filled with mud to 35', set plug, dumped 10 sacks cement; two sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 1 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stelbar Oil Corporation, Inc.

Address 310 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Bertrand M. Lester, Jr., Asst. Sec. (XXXXXXXXXXXX) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bertrand M. Lester Jr.  
310 Petroleum Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of May, 1961

My commission expires January 18, 1964

Notary Public.



LOG

Farm: Kostner "B"  
 Well No. 1  
 SE NW NW 6-29S-5W  
 Kingman County, Kansas

Drilling Commenced: 5-13-61  
 Drilling Completed: 5-25-61  
 Contractor: Stelbar Oil Corporation, Inc.  
 Owner: Stelbar Oil Corporation, Inc.

8-5/8" 262' cemented with 225 sacks  
 Elevation: 1411 DF

0	55	Sand and gravel
55	262	Broken Lime
262	1100	Shale and Shells
1100	1224	Shale and Lime
1224	1795	Lime and Shale
1795	1986	Shale and Shells
1986	2196	Shale and Lime
2196	2720	Lime and Shale
2720	2993	Lime
2993	3366	Lime and Shale
3366	3477	Lime
3477	3893	Lime and Shale
3893	3918	Mississippi Lime
3918	3986	Lime
	3986	D & A, RTD

Filled with mud to 240', set plug, dumped 20 sacks cement;  
 filled with mud to 35', set plug, dumped 10 sacks cement;  
 two sacks in rat hole.

**RECEIVED**  
 STATE CORPORATION COMMISSION

JUN 1 1961

CONSERVATION DIVISION  
 Wichita, Kansas