

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 35 Twp. 29S Rge. (E) 3 (W)

Location as "NE/CNW/SW" or footage from lines NE SE

Lease Owner Shawver Armour, Inc.

Lease Name Dalbom Well No. 1

Office Address 817 Central Building, Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed November 17 19 65

Application for plugging filed " " 19 "

Application for plugging approved " " 19 "

Plugging commenced " " 19 "

Plugging completed " " 19 "

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation Depth to top Bottom Total Depth of Well 3288 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface	water	0	227'	8 5/8"	227'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 225' w/38 Vis-mud

Added 1/2 sack hulls - Set a dry hole plug

Added 15 sacks cement.

Mudded hole from this point to 30'

Added hulls - set a dry hole plug - added

8 sacks cement

Capped rat hole w/12 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1965

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shawver Armour, Inc.
Address 817 Central Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

James M. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Armour, 817 Central Bldg.
Wichita, Kansas

Subscribed and Sworn to before me this 30th day of Nov, 19 65

My commission expires December 10, 1967

Claire Jones
Claire Jones Notary Public

DRILLER'S LOG

FARM NAME: DALBOM # 1 LOCATION: NE SE Sec. 35-29S-3W
Sedgwick Co., Ks.
CONTRACTOR: Shawver Armour, Inc. ELEVATION: 1336 KB
OWNER: Shawver Armour, Inc.
COMMENCED: November 10, 1965 COMPLETED: November 17, 1965
CASING RECORD: 227' 8 5/8" w/170 sacks cement & 4 sacks CC

FORMATION

TOPS

Shale & Lime 0 - 95
Hard Gr Shale & Lime 0
Stringers 227
Shale & Lime Stringers 815
Lime & Shale 1245
Shale & Lime 2195
Lime & Shale 2792
Stalnaker Sand 2930
Shale & Lime 3071
Lime & Shale 3114
Kansas City Lime 3127
Lime 3288

Iatan 2790
Stalnaker Sand 2808
Kansas City 3113

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1965

CONSERVATION DIVISION
WICHITA, KANSAS

Rotary Total Depth 3288

STATE OF KANSAS }
SEDGWICK COUNTY } ss

I, James M. Armour, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER ARMOUR, INC.

BY James M. Armour
James M. Armour

Subscribed and sworn to before me this
30th day of November, 1965

My commission expires Dec 10th, 1967

Claire Jones
Claire Jones Notary Public