
15-173-00459-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

SEDGWICK County. Sec. 28 Twp. 29 Rge. ____ (E) 3 (W)
Location as "NE/CNW¼SW¼" or footage from lines SE SE SE
Lease Owner SHAWVER-ARMOUR, INC.
Lease Name GRIER Well No. 1
Office Address 817 Central Building
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JUNE 13, 19 59
Application for plugging filed JUNE 13, 19 59
Application for plugging approved JUNE 13, 19 59
Plugging commenced JUNE 13, 19 59
Plugging completed JUNE 13, 19 59
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production ____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRED HAMPEL
Producing formation ____ Depth to top ____ Bottom ____ Total Depth of Well 4356 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE	WATER	0	195'	8-5/8"	226'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ____ feet to ____ feet for each plug set.

Heavy mud to 180'
#1 Plug 180' Howco Plug & 1/4 Sack Hulls
15 Sacks cement than heavy mud to 35'
#2 Plug 35' Howco Plug & 1/4 Sack Hulls and 13 Sacks cement
2 Sacks cement. Plug rat hole down 6'.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SHAWVER-ARMOUR, INC.
Address 817 Central Building - Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
H. D. SHAWVER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. D. Shawver
H. D. SHAWVER - PRESIDENT
817 Central Building
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 59

Marjorie Hall
MARJORIE HALL - Notary Public.

My commission expires December 29th, 1959

PLUGGING
FILE SEC. 28 T 29 R 3W
BOOK PAGE 60 LINE 44

6-44H

15-173-00459-0000

DRILLER'S LOG

FARM NAME: GRIER # 1

LOCATION: SE SE SE Sec. 28-29-3W
Sedgwick County, Kansas

CONTRACTOR: SHAWVER-ARMOUR, INC.

ELEVATION: 1333 K. B.

OWNER: SHAWVER-ARMOUR, INC.

COMMENCE: MAY 30, 1959

COMPLETED: JUNE 13, 1959

CASING RECORD: 226' 8-5/8" W/175 Sx. Cement 2% C.C.

FORMATION:		TOPS:	
Surface Clay	12	Stalnaker	2905
Rock, blue & gray shale	75	(Schlumberger Electric Tops)	
Red Rock & Shale	200	Kansas City	3162
Hard Shale & Lime	226	Base Kansas City	3363
Gray Rock & Shale	310	Mississippian Chert.	3796
Shale & Lime Streaks	605	Mississippian Lime	3808
Lime & Shale	945	Kinderhook Shale	4228
Anhydrite & Shale	1035	Simpson Sand	4337
Shale & Lime	1165		
Lime & Shale	1216		
Shale & Lime	2085		
Lime & Shale	2668		
Shale & Lime	2865		
Lime & Shale	3232		
Kansas City Lime & Shale	3288		
Kansas City Lime	3389		
Lime & Shale	3802		
Mississippian Lime & Chert.	4014		
Mississippian Lime	4225		
Lime & Shale	4338		
Simpson	4356 T.D.		

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1959
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I, H. D. Shawver, do hereby certify that the above log is a true and correct copy of the above captioned well as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

BY H. D. Shawver
H. D. SHAWVER

Subscribed and sworn to before me this 17th day of June, 1959.

My commission expires December 29th, 1959

Marjorie Hall
MARJORIE HALL-NOTARY PUBLIC

PLUGGING
FILE SEC 28 T 29 R 3W
BOOK PAGE 60 LINE 44