

1090590

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

10-4

API NUMBER 15- 129-21,292 - 0000
S/2 SW, SEC. 31, T 34 S, R 41 W/2

660 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Nusser A Well # 2

Operator: Anadarko Petroleum Corporation

County Morton 172.25

Name & Address P.O. Box 351

Well Total Depth 5300 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1445

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: Day: 4 Month: 10 Year: 19 95

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging (phone) 405-854-6515

work: 5 1/2" at 4978' w/150 sx cement, PBTD 4564', Perfs at 4720-42, 4449-64', FO tool @ 2714' w/150 sx cement

1st plug pump 25 sx cement with 2 sx hulls over perfs,

2nd plug pump 35 sx cement at 2400', 3rd plug pump 35 sx cement at 1475',

4th plug pump 35 sx cement at 650', 5th plug pump 10 sx cement at 30'.

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part

10-9-1995
CONSERVATION DIVISION
Wichita, Kansas

Operations Completed: Hour: 2 p.m. Day: 4 Month: 10 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement at 1 sx hulls over perfs,

2nd plug pulled to 2400' and pumped 35 sx cement,

3rd plug pulled to 1475' and pumped 35 sx cement,

4th plug pulled to 650' and pumped 35 sx cement,

5th plug pumped 10 sx cement at 30'.

Remarks: Used common cement by Sargent & Horton. Recovered 2411' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-10-95

Signed [Signature] (TECHNICIAN)

INV. NO. 43793