

To: B 1020832 12-19
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-21,153-0000
SE SE NE NW, SEC. 30, T. 34 S, R. 41 W/EK
4030 feet from S section line
2700 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Cyr A Well # 1
County Morton 72.96
Well Total Depth 2245 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1414

Abandoned Oil Well Gas Well X Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 19 Month: 12 Year: 19 94

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 2244' w/75 sx cement, PBSD 2244', Perfs at 2130-46'

1st plug pump 2 sx hulls and 25 sx cement at perfs, pressure up,

2nd plug pump 50 sx cement at 1440',

3rd plug pump 40 sx cement at 650',

4th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 4:45 p.m. Day: 19 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs, pressured up,

2nd plug pumped 50 sx cement at 1440',

3rd plug pumped 40 sx cement at 650',

4th plug pumped 10 sx cement at 40 to -4',

Mud between all plugs.

Remarks: Used common cement by Sargent & Horton. Recovered 1555' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(If you observe this plugging.)

INVOICED

Signed Glenn R Barlow
(TECHNICIAN)

DATE 1-2-95

INV. NO. 41941
12-19