

1100221

TO:

6-8

API NUMBER 15- 129-21512 - 0000

STATE CORPORATION COMMISSION C-NE-NW, SEC. 30, T 34 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME CRY CYR WELL # A-2

TECHNICIAN'S PLUGGING REPORT COUNTY MORTON .172.25

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 5300 FEET

OPERATOR: ANADARKO PETROLUM CO. PRODUCTION CSG: SIZE 5 1/2 FEET 4552

NAME AND P.O. BOX 351 SURFACE CSG 8 5/8" FEET 1501'

ADDRESS LIBERAL KS. 67905-0351

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR SARGENTS/HORTON LICENSE NUMBER 31151

ADDRESS RT 1 BOX 49AB TYRONE, OK. 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 A.M. DAY: 8 MONTH: 6 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENTS/HORTON (PHONE) 405-854-6515

WERE: 1-200# HULLS FOLLOWED BY 25 SX CEMENT 2-PULL 5 1/2 CASING TO 1530, SPOT 50 SX

PLUG 3- PULL 5 1/2 CASING TO 650' SPOT 40 SX PLUG. PULL TO 40' PUT 10 SX TO SURFACE.

PLUGGING PROPSAL RECEIVED BY: GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 8 MONTH: 6 YEAR: 1998

ACTUAL PLUGGING REPORT 1-PUMP 200# HULLS FOLLOWED BY 25 SX CEMENT FROM 4416'TO 4216'

2-PULL 5 1/2 CASING TO 1530'AND SPOT 50 SX CEMENT PLUG.

3-PULL 5 1/2 CASING TO 650' AND SPOT 40 SX CEMENT PLUG.

4-PULL CASING TO 40' AND PLACE 10 SX FROM 40' TO SURFACE.

REMARKS: USED ELTORO COMMON CEMENT BY SARGENTS. RECOVERED 2317' OF 5 1/2 CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID)NOT OBSERVE THIS PLUGGING.

SIGNED Gary L. Winters  
(TECHNICIAN) FORM CP-2/3

RECEIVED  
KANSAS CORPORATION COMMISSION

INVOICED

JUN 11 1998

DATE 6-15-98

CONSERVATION DIVISION  
WICHITA, KS

INV. NO. 50468  
6-8