

1100330

TO:
STATE CORPORATION COMMISSIONAPI NUMBER 15-129-10,259-~~2001~~ ^{000203 KAG} ₂₄₃
C NW NE SEC. 28, T 34 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WEBB A WELL # 4

TECHNICIAN'S PLUGGING REPORT 2/4

COUNTY MORTON 171.76

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 5285' FEET

OPERATOR: OXY USA INC

PRODUCTION CSG: SIZE 4 1/2" @ 5060' WITH 400 SX

NAME AND BOX 2528

SURFACE CASING: SIZE 8 5/8" @ 1453' WITH 675 SX

ADDRESS LIBERAL, KS 67950-2528

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CASING PULLING SERVICE LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 03 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM TERRY YODER

(COMPANY NAME) SARGENTS CASING PULLING SERVICE (PHONE) 316-624-7455

WERE: PERFS AT 4973-92

1ST PLUG SET CIBP AT 4880' WITH 2 SX CEMENT ON TOP. CIRCULATE HOLE WITH MUD.

2ND PLUG AT 1500' WITH 50 SX CEMENT DISPLACED WITH 9.0 MUD. 3RD PLUG AT 450' WITH 40 SX

CEMENT DISPLACED WITH 9.0 MUD. 4TH PLUG AT 0-50' WITH 15 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 04 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 4880' WITH 2 SX CEMENT ON TOP. CIRCULATE HOLE WITH MUD.

2ND PLUG AT 1500' WITH 50 SX CEMENT DISPLACED WITH 9.0 MUD. 3RD PLUG AT 450' WITH 40 SX

CEMENT DISPLACED WITH 9.0 MUD. 4TH PLUG AT 0-50' WITH 15 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 1503' OF 4 1/2" CASING. 2-18-2000

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) 18 2000

I (DID)

OBSERVE THIS PLUGGING

INVOICED

SIGNED

(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3

DATE 2/18/00

INV. NO.

061266