

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10329-00-00
Spot: CSESW Sec/Twnshp/Rge: 28-34S-41W
662 feet from S Section Line, 3307 feet from E Section Line
Lease/Unit Name: WEBB A Well Number: 5
County: MORTON Total Vertical Depth: 5220 feet

Operator License No.: 5447

Conductor Pipe: Size feet: 8 1/2

Op Name: OXY USA, INC.

Surface Casing: Size 8.625 feet: 1442 WITH 675 SX CMT

Address: PO BOX 27570 5 E GREENWAY PLZ STE
HOUSTON, TX 77227

Production: Size 5.5 feet: 5080 WITH 300 SX CMT

Liner: Size feet:

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 03/07/2002 1:55 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT ON BOTTOM. 1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

WitnessType: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 03/07/2002 4:30 PM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5010'. PERFS AT 4825-85'. PUMP 300# HULLS & 25 SX CMT ON BOTTOM. 1ST PLUG PULL TO 1450'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. 2ND PLUG PULL TO 500' & PUMP 40 SX CMT. 3RD PLUG PULL TO 40'. CIRCULATE 10 SX CMT TO SURFACE. STAYED FULL.

RECEIVED
MAR 13 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1502' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed 

(TECHNICIAN)

INVOICED MAR 11 2002

DATE 3-14-02

WV. NO. 2002061527 

Form 