

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-21522-00-00  
Spot: W2SWSW Sec/Twnshp/Rge: 20-30S-1W  
1320 feet from S Section Line, 330 feet from W Section Line  
Lease/Unit Name: REUSSER Well Number: 1  
County: SUMNER Total Vertical Depth: 3963 feet

Operator License No.: 5360  
Operator Name: BRANDT PRODUCTION COMPANY  
Address: 107 N MARKET, STE 914  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 413 275 SX CMT  
Production: Size 5.5 feet: 3958 50 SX CMT 128.80  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/02/2000 1:30 PM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN PETROLEUM & WELL PLUGGING COMPANY  
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETRO & WELL PLUGGI Phone: (316) 648-7710

Proposed Plugging Method: Sand back 50' above perms cap w/6sxs. Circulate cement from 450'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 11/02/2000 1:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Sand back to 3900 and capped w/6sxs of cement. Recovered 5 1/2" from 220' and pulled from the wellbore. Tubing was run to 450' and circulated cement to surface.

RECEIVED  
KCC DISTRICT #2

NOV 27 2000

WICHITA, KS

Remarks: ELMORE CEMENTING COMMON CEMENT.

Plugged through: TBG

District: 02

Signed [Signature]  
(TECHNICIAN)

INVOICED  
DATE 11/28/00  
INV. NO. 2001061013