

1050244

15-119-00020-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Completed 10-05-56
_____, SEC. 33, T 32 S, R. 30 W/E
990 feet from N/S section line
2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name Welcome A. Orr Well # 1

Operator: Diamond Shamrock Exploration Co.
Name & Address P. O. Box 631
Amarillo, TX 79173

County Meade
Well Total Depth 5688 184.86 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 2680

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 8:00 am Day: 11 Month: June Year: 19 84

Plugging proposal received from Troy Cody

(company name) Diamond Shamrock (phone) 806-378-3851

were: 7" set at 5687 Perfs 5638-42

- 1st plug pump 35 sx cement on bottom
- 2nd plug at 2700' with 50 sx cement
- 3rd plug at 1000' with 50 sx cement
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: noon Day: 11 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 9 5/8 set at 2680' Perfs 5638-42'

- 1st plug pumped 35 sx cement to bottom, 2nd plug at 2700' with 50 sx cement, 3rd plug
at 1000' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' --
cement to surface with 10 sx cement.

Remarks: Used Common sacked cement by Sargents. They recovered 2675 of 7" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-3-84
INV. NO. 2248
6-11

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1984

CONSERVATION DIVISION
Kansas

Signed Richard W. Lacey
(TECHNICIAN)