

To: 1 090285
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-14 - API NUMBER 15-Drilled 11/10/56
15-119-10137-0000

NW NW, SEC. 33, T. 32 S, R. 30 W/E
4620 feet from S section line
4623 feet from E section line
Lease Name Herman A Well # 1
County Meade 185.90
Well Total Depth 5720 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1804

TECHNICIAN'S PLUGGING REPORT
Operator License # 5229
Operator: Phillips Petroleum Company
Name & Address P.O. Box 358
Borger, TX 79008-0358

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 11:30 a.m. Day: 14 Month: 5 Year: 19 93
Plugging proposal received from Jeff Clarke
(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 5700' w/75 sx cement, PBTD 5668', Perfs at 5574-5590'
1st plug set CIBP at 5525' with 2 sx cement on top,
2nd plug pump 50 sx cement at 1830',
3rd plug pump 50 sx cement at 600',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:30 p.m. Day: 14 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5525' with 2 sx cement on top,
2nd plug spotted 50 sx cement at 1834' through tubing,
3rd plug pulled to 679' and spotted 50 sx cement,
4th plug pulled to 30' and spotted 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.) MAY 10 1993

INVOICED

DATE 5-20-93
INV. NO. 37746

Signed *[Signature]*
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas