

1041384

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-21,015-0000
S/2 SE NE SEC. 30, T 32 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HAYDEN "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT

1/19

COUNTY MEADE 190.45

OPERATOR LICENSE # 5123

WELL TOTAL DEPTH 5860 FEET

OPERATOR: PICKRELL DRILLING COMPANY, INC PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND 110 N MARKET, SUITE 205 SURFACE CASING: SIZE 8 5/8" @ 1635' WITH SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PICKRELL DRILLING CO., INC LICENSE NUMBER 5123

ADDRESS 110 N MARKET, SUITE 205, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 5:00 AM DAY: 19 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MIKE KERNS

(COMPANY NAME) PICKRELL DRILLING (PHONE) 316-262-8427

WERE:

1ST PLUG AT 1660' WITH 50 SX CEMENT.

2ND PLUG AT 600' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. NO MOUSE HOLE.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 9:00 AM DAY: 19 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1660' WITH 50 SX CEMENT.

2ND PLUG AT 600' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. NO MOUSE HOLE. JAN 25 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

INVOICED

DATE 1/25/00

RECEIVED STATE CORPORATION COMMISSION

NOV 19 06/179

JAN 25 2000

CONSERVATION DIVISION
Wichita, Kansas