

To: 1 090775 1-31
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-119-20,969-0000
SE NE, SEC. 25, T 32 S, R 30 W/X
1980 feet from NW section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 4549
Operator: Anadarko Petroleum Corporation
Name:
Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Pace A Well # 1
County Meade 199.87
Well Total Depth 6150 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1640

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2 p.m. Day: 30 Month: 1 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 5700', PBD 5644', Perfs at 5558-94'
1st plug pump 2 sx hulls and 25 sx cement on bottom,
2nd plug load hole with mud and pump 30 sx cement at cut off,
3rd plug at 1660' with 50 sx cement, 4th plug at 650' with 40 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 3 p.m. Day: 31 Month: 1 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement on bottom,

Loaded hole with mud, 2-10-97
2nd plug pumped 30 sx cement at 3101';
3rd plug pumped 50 sx cement at 1660',
4th plug pumped 40 sx cement at 650',
5th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Sargent & Horton. Recovered 3101' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

Signed [Signature] (TECHNICIAN)

DATE 2-11-97

INV. NO. 47541