

To: 1 020492
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,088-00-01 235 R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Suite 205
Wichita, KS 67202

C SE SW, SEC. 21, T. 32 S, R. 31 W/E
660 feet from S section line

3300 feet from E section line

Lease Name Siemens Hospital Foundation Well # 1-21

County Seward 153.07

Well Total Depth 4710 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1594

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 17 Month: 8 Year: 19 92

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

was: 4 1/2" at 4498' w/150 sx cement, PBDT 4473', Perfs at 4404-06'

1st plug pump 20 sx cement and 1 sx hulls on bottom,

2nd plug pump 50 sx cement at 1610',

3rd plug pump 40. sx cement at 650',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4 p.m. Day: 20 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs,

2nd plug pumped 50 sx cement at 1620',

3rd plug pumped 30 sx cement at 600',

4th plug pumped 10 sx cement at 40 to -4',

Mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 2790' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

~~XXXX~~ did not observe this plugging.

DATE 9-29-92

INV. NO. 36253

Signed Glean R. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1992

CONSERVATION DIVISION
Wichita, Kansas

OCT 28 1992