

1 020360

3-13

204

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- 175-21,047-0000  
SE SE, SEC. 19, T 32, S, R 31 W/E  
660 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711

Lease Name Simmonds Well # 1-19

Operator: Shepler & Thomas, Inc.

County Seward 195.97

Name & Address P.O. Box 1162

Well Total Depth 6030 feet

Liberal, KS 67905-1162

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1627

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 12 Month: 3 Year: 19 91

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 5790' w/230 sx cement, PBD 5720', Perfs at 5084-90'

1st plug pump 1 sx hulls and 25 sx cement at perfs,

2nd plug pump 30 sx cement at cut off, 3rd plug pump 50 sx cement at 1650',

4th plug pump 40 sx cement at 700',

5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:30 p.m. Day: 13 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 30 sx cement at perfs, pressured to 2000#, displaced with mud,

2nd plug pumped 50 sx cement at 1657', displaced with mud,

3rd plug pumped 30 sx cement at 700', displaced with mud,

4th plug pumped 10 sx cement at 35-0'.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 20 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3000' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Glenn S. Barlow (TECHNICIAN)

DATE 4-3-91

INV. NO. 31309

3-13