

1 020318

6-27

API NUMBER 15-175-21,130-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

S/2 NE NW, SEC. 16, T 32 S, R 31 W/E

4290 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 3908

Lease Name Beck Well # 1-16

Operator: Parker and Parsley Petroleum

County Seward 185.25

Name & Address P.O. Box 3178

Well Total Depth 5700 feet

Midland, TX 79702

Conductor Pipe: Size 12 3/4 feet 603

Surface Casing: Size 8 5/8 feet 1769

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pool Well Service License Number \_\_\_\_\_

Address P.O. Box 1063, Ulysses, KS 67880

Company to plug at: Hour: 2:30 p.m. Day: 26 Month: 6 Year: 19 90

Plugging proposal received from Clyde Johnson

(company name) Pool Well Service (phone) 316-356-2060

were: 4 1/2" at 5700', PBD 5130', Perfs at 4966-5066'

1st plug pump 50 sx cement at 1779-1679',

2nd plug at 700-612' with 30 sx cement,

3rd plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 27 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx celleflex and 10 sx cement at perf. top.

Top of cement 4956' Pressured to 600#, let set six hours.

2nd plug pumped 50 sx cement at 1770',

3rd plug 30 sx cement at 700',

4th plug pumped 10 sx cement at 40-0',

5th plug ran 1" in annulus of 12 3/4" X 8 5/8" and filled to surface.

Plugs set with tubing.

Remarks: Recovered 2500' of 4 1/2" casing. Used Class H cement by D & S.

(if additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 1990  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

observe this plugging.

Signed Steven L. Barlow (TECHNICIAN)

DATE 7-9-90

INV. NO. 28561

6-27